

Standardized Comparison of ME generators

Gervasio Gómez
Instituto de Física de Cantabria / CSIC



IFCA
INSTITUTO DE FÍSICA DE CANTABRIA



IPPP MC Workshop. Durham, January 2003

Motivation

- Several ME generators available:
 - ALPGEN, MadGraph, GR@PPA, CompHEP, MCFM, others
 - Many processes including W/Z + light or heavy jet-partons
 - Define a common set of inputs, cuts and processes to make comparisons
- Useful
 - Authors get feedback from users
 - Improvements in code
 - Better user interfaces
 - Implementation of new processes
 - Good way to determine if there are bugs
 - Agreement \Rightarrow trust

“comparison” ME inputs

Parameter	value
M_z	91.188 GeV
M_w	80.41 GeV
G_F	1.16639×10^{-5} GeV $^{-2}$
$\sin^2\theta_w$	0.2224
α_{em}	1/132.43
Γ_w	2.047 GeV
Γ_z	2.445 GeV
g	0.6532
g'	0.7407
CKM: $V_{ud} = V_{cs}$	$\text{sqrt}(0.95)$
CKM: $V_{us} = -V_{cd}$	$\text{sqrt}(0.05)$
CKM: $V_{ub} = V_{cb}$	0.0
CKM: $V_{ts} = V_{td}$	0.0
CKM: V_{tb}	1.0

“comparison” ME inputs


Parameter	value
beam	p-pbar
sqrt(s)	1.96 TeV
Q^2	M_v^2
PDF	CTEQ5L (parametric)
$\alpha_s(M_z)$	0.127
m_t	175.0 GeV
m_b	4.75 GeV
m_c	1.55 GeV
m_τ	1.777 GeV

“comparison” cuts

- Charged leptons
 - Z/γ^* only, l^+l^- pairs: $50 < m_{ll} < 200$ GeV
 - No other cuts
- Neutrinos
 - No cuts
- Jet-partons
 - $P_T > 10$ GeV
 - $|\eta| < 2.5$
- Separation between particles/partons
 - jj: $\Delta R_{JJ} > 0.4$ (j=jet parton)
 - jl, ll: no cut in ΔR (l=any lepton)


$\sigma(W+jets)$ (pb)

ME-MC	W+0j	W+1j	W+2j	W+3j	W+4j	W+5j
ALPGEN	2046 ± 1	522.6 ± 0.6	146.1 ± 0.3	41.5 ± 0.2	11.55 ± 0.07	3.13 ± 0.02
GRAPPA	2042 ± 4	525.4 ± 0.6	146.8 ± 0.3	40.2 ± 0.3		
MadGraph	2044 ± 5	525.4 ± 1.1	146.1 ± 0.3	41.8 ± 0.1		
MCFM(LO)	2044 ± 1	526.3 ± 0.5	147.2 ± 0.3	41.8 ± 0.2		




$\sigma(Z+\text{jets}) \text{ (pb)}$

ME-MC	Z+0j	Z+1j	Z+2j	Z+3j	Z+4j	Z+5j
ALPGEN	198.0 ± 0.2	53.72 ± 0.06	14.76 ± 0.05	4.09 ± 0.02	1.13 ± 0.01	0.292 ± 0.002
GRAPPA	198.1 ± 0.2	54.02 ± 0.06	15.07 ± 0.02			
MadGraph	198.9 ± 0.7	53.5 ± 0.2	14.70 ± 0.04	4.079 ± 0.009		
MCFM(LO)	198.2 ± 0.1	53.80 ± 0.05	14.79 ± 0.03	4.11 ± 0.02		



$\sigma(Wbb+jet)$ (fb)

ME-MC	Wbb+0j	Wbb+1j	Wbb+2j	Wbb+3j
ALPGEN	1170 ± 2	596 ± 2	253 ± 2	100 ± 1
GRAPPA	1178 ± 3			
MadGraph	1175 ± 8	602 ± 2	251.1 ± 0.7	
MCFM(LO)	1175 ± 3			



$\sigma(Zbb+jet)$ (fb)

ME-MC	Zbb+0j	Zbb+1j	Zbb+2j	Zbb+3j
ALPGEN	181.7 ± 0.4	93.5 ± 0.5	37.6 ± 0.4	12.8 ± 0.6
MadGraph	182.5 ± 1.2	92.7 ± 0.4		
MCFM(LO)	182.2 ± 0.5			

